

Client
Neometro

Date
10 July 2024

Planning

Transport

Urban Design

Waste Management

Waste Management Plan

97 Alma Road, St Kilda East

ratio:

ratio.com.au

Project
97 Alma Road, St Kilda East

Prepared for
Neometro

Our reference
19329W-R02F02

Directory path <https://ratioconsultants1.sharepoint.com/sites/19329W/Shared Documents/9. Reports/19329W-R02F02.docx>

Version	Date	Issue	Prepared by	Checked by
R01D01	4/11/2022	Town Planning - Draft	W Psiwa	M Fairlie
R01F01	28/11/2022	Town Planning - Final	W Psiwa	M Fairlie
R02F01	3/06/2024	Town Planning - Amended Plans + RFI Response	W Psiwa	L Harris
R02F02	10/07/2024	Town Planning - Amended Plans	W Psiwa	L Harris

Ratio Consultants Pty Ltd

This work is copyright. Apart from any use as permitted under Copyright Act 1968, no part may be reproduced without written permission of Ratio Consultants Pty Ltd.

Disclaimer: neither Ratio Consultants Pty Ltd nor any member or employee of Ratio Consultants Pty Ltd takes responsibility in anyway whatsoever to any person or organisation (other than that for which this report is being prepared) in respect of the information set out in this report, including any errors or omissions therein. Ratio Consultants Pty Ltd is not liable for errors in plans, specifications, documentation or other advice not prepared or designed by Ratio Consultants Pty Ltd.

Table of Contents

Section	Page No.
1. Introduction	4
1.1. Project Details	4
1.2. Purpose	5
1.3. Limitations	5
1.4. Relevant Guidelines and Policies	5
2. Operational Waste Management Guide	6
2.1. Recycling Victoria: A New Economy	6
2.2. Guide for Residents of the Apartments	7
2.3. Guide for Residents of the Townhouses	8
2.4. Guide for the F&B Operator / Staff	9
2.5. Building Manager Responsibilities	10
2.6. Waste System Education	10
2.7. Waste Management Plan Revisions	10
3. Waste Volume Assessment Details	11
3.1. Residential Waste Volume Assessment	11
3.2. Commercial Waste Volume Assessment	14
4. Waste Storage Details	16
4.1. Residential Waste Storage Requirements	16
4.2. Residential Waste Storage Layouts	17
4.3. Commercial Waste Storage Requirements	19
4.4. Commercial Waste Storage Layout	19
5. Waste Collection Details	20
5.1. Residential Waste Collection Requirements	20
5.2. Commercial Waste Collection Requirements	21
5.3. Waste Collection Methodology	21
5.4. Waste Collection Time	21
6. Design Standards	22

6.1. Bin Room Design Requirements	22
6.2. Bin Colour and Signage Requirements	23
6.3. Internal Waste Receptacle Requirements	23

Appendices

Appendix A : Plans Assessed	24
Appendix B : Waste Collection Vehicle Swept Path Assessment	25

Table of Figures

Figure 2.1: The Circular Economy	6
Figure 4.2: Northern Residential Bin Room Waste Storage Layout	17
Figure 4.3: Southern Residential Bin Room Waste Storage Layout	18
Figure 4.4: F&B Bin Room Waste Storage Layout	19

1. Introduction

1.1. Project Details

Site Address

97 Alma Road, St Kilda East

Local Council

Port Phillip City Council - Phone: (03) 9205 5555

Planning Application Number

PDPL/00823/2022

Development Summary

Land Use Type	Building Section	Waste Source	Quantity
Residential	Northern	1-Bedroom Apartment	10 dwellings
		2-Bedroom Apartment	24 dwellings
		3-Bedroom Apartment	13 dwellings
		Total	47dwellings
	Southern	3-Bedroom Townhouse	20 dwellings
Total		20 dwellings	
Commercial	Northern	F&B Premises	33 m ²

1.2. Purpose

This Waste Management Plan has been prepared to address Council's RFI as outlined below:

- Amended basement ramp to avoid encroachment of the 300mm clearance lines for waste truck collection.
- Allocation of a commercial garbage bin of a minimum size of 660 Litres or alteration to the Waste Management Plan to require an increase in the frequency of commercial garbage collection for the food and drink premises.
- The northern bin room door is either a roller door or shown to open inwards to ensure ease of transportation of skip bins to and from the collection point.
- Prior to the endorsement of plans under Condition 1 of this permit, a Waste Management Plan (WMP) must be submitted to and approved by the Responsible Authority. The WMP must be generally in accordance with the WMP submitted with the application by Ratio Consultants dated 28 November 2022 but amended to include nomination of a responsible party to ensure future residents are informed of the Waste Management Plan provisions relating to bin collection, hard waste removal and other waste facilities in the building and to include changes required by Condition 1 in relation to waste management.

1.3. Limitations

Waste management arrangements during the construction and fit-out stages of the development, and on-going operation and monitoring of the waste management arrangements for the development following the occupation of the development are outside the scope of this Waste Management Plan.

1.4. Relevant Guidelines and Policies

Relevant policies and guidelines considered as part of the preparation of this Waste Management Plan include:

- Australian Government – National Waste Policy: Less Waste, More Resources (2018).
- Victorian Government – Recycling Victoria: A New Economy (2020).
- Sustainability Victoria – Better Practice Guide for Waste Management and Recycling in Multi-Unit Developments (2018).
- Port Phillip City Council – Guidelines for Preparing a Waste Management Plan (2019).
- EPA Victoria – Noise Control Guidelines (2021).

2. Operational Waste Management Guide


2.1. Recycling Victoria: A New Economy

The Victorian Government’s Recycling Victoria: A New Economy was released in 2020 and sets out strategies to reduce the amount of waste generated in Victoria and increase the amount of materials for recycling and reprocessing to reduce damage to the environment caused by waste.

Ongoing education and dedicated ongoing management services are critical factors in encouraging users to continue to use the services and systems as intended. The future Occupiers of the development shall promote the above strategy where practicable and encourage users to participate in minimising the impact of waste on the environment. In particular, consideration should be made to the circular economy as shown in Figure 2.1 below.

A circular economy continually seeks to reduce the environmental impacts of production and consumption, while enabling economic growth through more productive use of natural resources.

Figure 2.1: The Circular Economy



Source: *Recycling Victoria: A New Economy*

Establishment of waste reduction and recycling targets, including conducting periodic waste audits, keeping records of waste streams, and monitoring of the quantity of recyclables found in landfill-bound bins. The results of such audits shall be shared with users to encourage further reductions in waste where possible

2.2. Guide for Residents of the Apartments

General Waste Disposal

- Residents shall place general waste into a dedicated general waste receptacle (to be provided by Building Management).
- Residents shall empty their general waste receptacle into the general waste collection bins located within the northern residential bin room on basement level when full.
- Residents shall ensure that general waste is placed within tied bags (biodegradable material recommended) prior to being placed into the general waste collection bins.

Recycling Disposal

- Residents shall place recycling into a dedicated recycling receptacle (to be provided by Building Management).
- Residents shall empty their recycling receptacle into the recycling collection bins located within the northern residential bin room on basement level when full.
- Residents shall ensure that bottles, cans, and containers are rinsed, cardboard is flattened, and lids/packaging are separated as per the Australasian Recycling Label instructions (visit: <https://recyclingnearyou.com.au/arl/>), prior to being placed into the recycling collection bins. Recycling must not be bagged.

Organics Disposal

- Residents shall place food scraps into a dedicated organics caddy (to be provided by Building Management).
- Residents shall empty their organics caddy into the organics collection bins located within the northern residential bin room on basement level when full.
- Residents shall ensure that organics are unbagged or placed within approved compostable bags prior to being placed into the organics collection bins.

Glass Disposal

- Residents shall place glass into a dedicated glass receptacle (to be provided by Building Management).
- Residents shall empty their glass receptacle into the glass collection bins located within the northern residential bin room on basement level when full.
- Residents shall ensure that glass bottles and jars are rinsed, and lids/packaging are separated as per the Australasian Recycling Label instructions (visit: <https://recyclingnearyou.com.au/arl/>), prior to being placed into the glass collection bins. Glass must not be bagged.

Disposal of Other Waste Streams

- Soft Plastics: residents are encouraged to take soft plastics to a nearby drop-off location. Visit this link for further details: <https://redcycle.net.au/where-to-redcycle/>.
- Hard waste and e-waste: residents shall place hard waste and e-waste items at the marked location provided within the northern residential bin room on basement level. Building Management shall arrange for hard waste and e-waste to be collected directly from the northern residential bin room by a private contractor on an as-required basis.

2.3. Guide for Residents of the Townhouses

General Waste Disposal

- Residents shall place general waste into a dedicated general waste receptacle (to be provided by Building Management).
- Residents shall empty their general waste receptacle into the general waste collection bins located within the southern residential bin room on basement level when full.
- Residents shall ensure that general waste is placed within tied bags (biodegradable material recommended) prior to being placed into the general waste collection bins.

Recycling Disposal

- Residents shall place recycling into a dedicated recycling receptacle (to be provided by Building Management).
- Residents shall empty their recycling receptacle into the recycling collection bins located within the southern residential bin room on basement level when full.
- Residents shall ensure that bottles, cans, and containers are rinsed, cardboard is flattened, and lids/packaging are separated as per the Australasian Recycling Label instructions (visit: <https://recyclingnearyou.com.au/arl/>), prior to being placed into the recycling collection bins. Recycling must not be bagged.

Organics Disposal

- Residents shall place food scraps into a dedicated organics caddy (to be provided by Building Management).
- Residents shall empty their organics caddy into the organics collection bins located within the southern residential bin room on basement level when full.
- Residents shall ensure that organics are unbagged or placed within approved compostable bags prior to being placed into the organics collection bins.

Glass Disposal

- Residents shall place glass into a dedicated glass receptacle (to be provided by Building Management).
- Residents shall empty their glass receptacle into the glass collection bins located within the southern residential bin room on basement level when full.
- Residents shall ensure that glass bottles and jars are rinsed, and lids/packaging are separated as per the Australasian Recycling Label instructions (visit: <https://recyclingnearyou.com.au/arl/>), prior to being placed into the glass collection bins. Glass must not be bagged.

Disposal of Other Waste Streams

- Soft Plastics: residents are encouraged to take soft plastics to a nearby drop-off location. Visit this link for further details: <https://redcycle.net.au/where-to-redcycle/>.
- Hard waste and e-waste: residents shall place hard waste and e-waste items at the marked location provided within the southern residential bin room on basement level. Building Management shall arrange for hard waste and e-waste to be collected directly from the southern residential bin room by a private contractor on an as-required basis.

2.4. Guide for the F&B Operator / Staff

General Waste Disposal

- Staff shall place general waste into dedicated general waste receptacles (to be provided by the F&B Operator).
- Staff shall empty the general waste receptacles into the general waste collection bins located within the F&B bin room on basement level when full.
- Staff shall ensure that general waste is placed within tied bags (biodegradable material recommended) prior to being placed into the general waste collection bins.

Recycling Disposal

- Staff shall place recycling into dedicated recycling receptacles (to be provided by the F&B Operator).
- Staff shall empty the recycling receptacles into the recycling collection bins located within the F&B bin room on basement level when full.
- Staff shall ensure that bottles, cans, and containers are rinsed, cardboard is flattened, and lids/packaging are separated as per the Australasian Recycling Label instructions (visit: <https://recyclingnearyou.com.au/arl/>), prior to being placed into the recycling collection bins. Recycling must not be bagged.

Organics Disposal

- Staff shall place food scraps into dedicated organics caddies (to be provided by the F&B Operator).
- Staff shall empty the organics caddies into the organics collection bins located within the F&B bin room on basement level when full.
- Staff shall ensure that organics are unbagged or placed within approved compostable bags prior to being placed into the organics collection bins.

Glass Disposal

- Staff shall place glass into dedicated glass receptacles (to be provided by the F&B Operator).
- Staff shall empty the glass receptacles into the glass collection bins located within the F&B bin room on basement level when full.
- Staff shall ensure that glass bottles and jars are rinsed, and lids/packaging are separated as per the Australasian Recycling Label instructions (visit: <https://recyclingnearyou.com.au/arl/>), prior to being placed into the glass collection bins. Glass must not be bagged.

Disposal of Other Waste Streams

- Soft Plastics: the F&B Operator is encouraged to arrange for soft plastics to be taken to a nearby drop-off location. Visit this link for further details: <https://redcycle.net.au/where-to-redcycle/>.
- Hard waste and e-waste: the F&B Operator shall arrange for hard waste and e-waste items to be placed at the marked location provided within the F&B bin room on basement level. The F&B Operator shall arrange for hard waste and e-waste to be collected directly from the F&B bin room by a private contractor on an as-required basis.

2.5. Building Manager Responsibilities

- Ongoing management of the waste system including the maintenance of the bin rooms and associated equipment and components, to the satisfaction of users and the relevant authority, and in accordance with relevant manufacturer specifications. When required, Building Management shall engage an appropriate contractor to conduct services, replacements or upgrades.
- Engage and manage the waste collection contractor.
- Developing and implementing adequate safe operating procedures (including the preparation of Safe Work Method Statements).
- Securing the bin room to prevent theft and vandalism of bins.
- Removal of litter from all communal areas on a regular basis.
- Publish and distribute information or 'house rules' to ensure that building users are familiar about the waste management system.
- Inform users that bagged recycling and glass is not permitted.

2.6. Waste System Education

Building Management shall publish/ distribute rules/ information/ educational material to:

- Inform users about the waste management system.
- Improve facility management results, to reduce equipment damage, reduce littering, and to achieve better cleanliness.
- Advise users to sort and recycle waste with care to reduce contamination of recyclables.

2.7. Waste Management Plan Revisions

From time to time, due to changes in legislative requirements, changes in the development's needs and/or waste patterns (such as waste composition, volume, or distribution), or to address unforeseen operational issues, Building Management shall be responsible for coordinating the necessary Waste Management Plan revisions, including (on an as-required basis):

- A waste audit and new waste management strategy.
- Revision of the waste system (bin size / quantity / waste streams / collection frequency / update of equipment).
- Revision of the services provided by the waste collection contractor(s).
- Re-education of users.
- Any necessary statutory / regulatory requirements / approvals.

3. Waste Volume Assessment Details

3.1. Residential Waste Volume Assessment

Port Phillip City Council's 'Guidelines for Preparing a Waste Management Plan' specifies the following waste generation rates applicable to the residential component of the development:

1-Bedroom Dwelling

- General Waste: 80 L/dwelling/week
- Recycling: 80 L/dwelling/week

2-Bedroom Dwelling

- General Waste: 100 L/dwelling/week
- Recycling: 100 L/dwelling/week

3/4-Bedroom Dwelling

- General Waste: 120 L/dwelling/week
- Recycling: 120 L/dwelling/week

To allow for the separation of organics and glass from the general waste and recycling streams (respectively), the following modified waste generation rates are considered appropriate (adopting a 75 : 20 split for general waste : organics and a 70 : 30 split for recycling : glass):

1-Bedroom Dwelling

- General Waste: 60 L/dwelling/week
- Organics: 20 L/dwelling/week
- Recycling: 56 L/dwelling/week
- Glass: 24 L/dwelling/week

2-Bedroom Dwelling

- General Waste: 75 L/dwelling/week
- Organics: 25 L/dwelling/week
- Recycling: 70 L/dwelling/week
- Glass: 30 L/dwelling/week

3/4-Bedroom Dwelling

- General Waste: 90 L/dwelling/week
- Organics: 30 L/dwelling/week
- Recycling: 84 L/dwelling/week
- Glass: 36 L/dwelling/week

Applying the above modified waste generation rates, the waste volume estimates for the residential component of the development are outlined in Tables 3.1 to 3.4 below.

Table 3.1: Residential General Waste Volume Estimates

Land Use Type	Building Section	Waste Source	Quantity	General Waste Generation Rate	General Waste Volume
Residential	Northern	1-Bedroom Apartment	10 dwellings	60 L/dwelling/week	600 L/week
		2-Bedroom Apartment	24 dwellings	75 L/dwelling/week	1,800 L/week
		3-Bedroom Apartment	13 dwellings	90 L/dwelling/week	1,170 L/week
		Total			
	Southern	3-Bedroom Townhouse	20 dwelling	90 L/dwelling/week	1,800L/week
		Total			

Table 3.2: Organics Volume Estimates

Land Use Type	Building Section	Waste Source	Quantity	Organics Generation Rate	Organics Volume
Residential	Northern	1-Bedroom Apartment	10 dwellings	20 L/dwelling/week	200 L/week
		2-Bedroom Apartment	24 dwellings	25 L/dwelling/week	600 L/week
		3-Bedroom Apartment	13 dwellings	30 L/dwelling/week	390 L/week
		Total			
	Southern	3-Bedroom Townhouse	20 dwelling	30 L/dwelling/week	600 L/week
		Total			

Table 3.2: Residential Recycling Volume Estimates

Land Use Type	Building Section	Waste Source	Quantity	Recycling Generation Rate	Recycling Volume
Residential	Northern	1-Bedroom Apartment	10 dwellings	56 L/dwelling/week	560 L/week
		2-Bedroom Apartment	24 dwellings	70 L/dwelling/week	1,680 L/week
		3-Bedroom Apartment	13 dwellings	84 L/dwelling/week	1,092 L/week
		Total			
	Southern	3-Bedroom Townhouse	20 dwelling	84 L/dwelling/week	1,680 L/week
		Total			

Table 3.2: Residential Glass Volume Estimates

Land Use Type	Building Section	Waste Source	Quantity	Glass Generation Rate	Glass Volume
Residential	Northern	1-Bedroom Apartment	10 dwellings	24 L/dwelling/week	240 L/week
		2-Bedroom Apartment	24 dwellings	30 L/dwelling/week	720 L/week
		3-Bedroom Apartment	13 dwellings	36 L/dwelling/week	468 L/week
		Total			
	Southern	3-Bedroom Townhouse	20 dwelling	36 L/dwelling/week	720 L/week
		Total			

3.2. Commercial Waste Volume Assessment

Port Phillip City Council's 'Guidelines for Preparing a Waste Management Plan' specifies the following waste generation rates applicable to the commercial component of the development:

Café

- General Waste: 300 L/100m²/day
- Recycling: 200 L/100m²/day

To allow for the separation of organics and paper & cardboard from the general waste and recycling streams (respectively), the following modified waste generation rates are considered appropriate (adopting a 80 : 20 split for general waste : organics and a 50 : 50 split for recycling : paper & cardboard):

Café

- General Waste: 240 L/100m²/day
- Organics: 60 L/100m²/day
- Recycling: 100 L/100m²/day
- Paper & Cardboard: 100 L/100m²/day

Applying the above modified waste generation rates, the waste volume estimates for the commercial component of the development are outlined in Tables 3.5 to 3.8 below.

Table 3.5: Commercial General Waste Volume Estimates

Land Use Type	Building Section	Waste Source	Quantity	General Waste Generation Rate	General Waste Volume
Commercial	Northern	F&B Premises	33 m ²	240 L/100m ² /day	554 L/week

Table 3.6: Organics Volume Estimates

Land Use Type	Building Section	Waste Source	Quantity	Organics Generation Rate	Organics Volume
Commercial	Northern	F&B Premises	33 m ²	60 L/100m ² /day	139 L/week

Table 3.7: Commercial Recycling Volume Estimates

Land Use Type	Building Section	Waste Source	Quantity	Recycling Generation Rate	Recycling Volume
Commercial	Northern	F&B Premises	33 m ²	100 L/100m ² /day	231 L/week

Table 3.8: Commercial Paper & Cardboard Volume Estimates

Land Use Type	Building Section	Waste Source	Quantity	Paper & Cardboard Generation Rate	Paper & Cardboard Volume
Commercial	Northern	F&B Premises	33 m ²	100 L/100m ² /day	231 L/week

4. Waste Storage Details

4.1. Residential Waste Storage Requirements

The waste storage requirements for the residential component of the development are outlined in Table 4.1 below.

Table 4.1: Residential Waste Storage Requirements

Waste Storage Location	Waste Stream	Bin Size (L)	Quantity	Height per bin (mm)	Width per bin (mm)	Depth per bin (mm)	Footprint (m ²)
Northern Residential Bin Room	General Waste	1100	2	1330	1240	1070	2.65
	Organics	120	5	930	480	545	1.31
	Recycling	1100	2	1330	1240	1070	2.65
	Glass	240	3	1060	585	730	1.28
	Hard Waste & E-waste	2 sqm storage area					2.00
	Total Footprint (Excluding Circulation)						
Southern Residential Bin Room	General Waste	1100	1	1330	1240	1070	1.33
	Organics	120	3	930	480	545	0.78
	Recycling	1100	1	1330	1240	1070	1.33
	Glass	240	2	1060	585	730	0.85
	Hard Waste & E-waste	2 sqm storage area					2.00
	Total Footprint (Excluding Circulation)						

4.2. Residential Waste Storage Layouts

The proposed waste storage layouts for the residential component of the development are shown in Figures 4.1 and 4.2 below.

Figure 4.2: Northern Residential Bin Room Waste Storage Layout





Figure 4.3: Southern Residential Bin Room Waste Storage Layout



Note: The doors for the northern and southern bin rooms open inwards to ensure ease of transportation of bins to and from the collection point.

4.3. Commercial Waste Storage Requirements

The waste storage requirements for the commercial component of the development are outlined in Table 4.1 below.


Table 4.2: Commercial Waste Storage Requirements

Waste Storage Location	Waste Stream	Bin Size (L)	Quantity	Height per bin (mm)	Width per bin (mm)	Depth per bin (mm)	Footprint (m ²)
F&B Bin Room	General Waste	660	1	1200	1260	780	0.98
	Organics	240	1	930	480	545	0.43
	Recycling	240	1	930	480	545	0.43
	Paper & Cardboard	240	1	930	480	545	0.43
	Hard Waste & E-waste	1 sqm storage area					1.00
Total Footprint (Excluding Circulation)							3.26

4.4. Commercial Waste Storage Layout

The proposed waste storage layout for the commercial component of the development is shown in Figure 4.3 below.

Figure 4.4: F&B Bin Room Waste Storage Layout



5. Waste Collection Details

5.1. Residential Waste Collection Requirements

The waste collection requirements for the residential component of the development are outlined in Table 5.1 below.

Table 5.1: Residential Waste Collection Requirements

Waste Storage Location	Waste Stream	Volume (L/week)	Bin Size (L)	Quantity	Collection Frequency	Capacity (L/week)
Northern Residential Bin Room	General Waste	3,570	1100	2	Twice weekly	4,400
	Organics	1,190	120	5	Twice weekly	1,200
	Recycling	3,332	1100	2	Twice weekly	4,400
	Glass	1,428	240	3	Twice weekly	1,440
	Hard Waste & E-waste	-	-	2 sqm storage area	As required	-
Southern Residential Bin Room	General Waste	1,800	1100	1	Twice weekly	2,200
	Organics	600	120	3	Twice weekly	720
	Recycling	1,680	1100	1	Twice weekly	2,200
	Glass	720	240	2	Twice weekly	960
	Hard Waste & E-waste	-	-	2 sqm storage area	As required	-

5.2. Commercial Waste Collection Requirements

The waste collection requirements for the commercial component of the development are outlined in Table 5.2 below.

Table 5.2: Commercial Waste Collection Requirements

Waste Stream	Volume (L/week)	Bin Size (L)	Quantity	Collection Frequency	Capacity (L/week)
General Waste	554	660	1	Weekly	660
Organics	139	240	1	Weekly	240
Recycling	231	240	1	Weekly	240
Paper & Cardboard	231	240	1	Weekly	240
Hard Waste & E-waste	-	-	1 sqm storage area	As required	-

5.3. Waste Collection Methodology

The proposed waste collection methodology for the development is outlined below:

- Waste shall be collected from the basement level car park by a private waste collection contractor.
- The nominated waste collection vehicle is the 6.4-metre-long rear loader, which has a travel height clearance requirement of 2.2 metres and an operational height clearance requirement of 2.5 metres. No height clearance issues have been identified within the basement level car park.
- A swept path assessment has been prepared using Autodesk Vehicle Tracking Software demonstrating that the nominated waste collection vehicle can undertake waste collection from the basement level car park in a suitable manner, entering and exiting the site in a forward direction (refer to Appendix B).
- The waste collection contractor shall wheel the bins from the bin rooms to the waste collection vehicle for collection and return the bins to the bin rooms immediately after collection is complete.
- The waste collection contractor shall also be responsible for the development of a Safe Work Method Statement (SWMS) to ensure safety is considered for every aspect of the collection process.
- Hard waste and e-waste shall be collected on an as-required basis by a private contractor.

5.4. Waste Collection Time

Waste collection shall be undertaken in accordance with EPA Victoria's 'Noise Control Guidelines', as stipulated below:

- Between 7:00am and 8:00pm Monday to Saturday; and
- Between 9:00am and 8:00pm Sunday and public holidays.

Further to the above, it is recommended that waste collection is undertaken outside of peak AM and PM periods to minimise disruption to vehicles entering/exiting the site (i.e., between 10:00am and 3:00pm on weekdays).

6. Design Standards

6.1. Bin Room Design Requirements

The bin rooms shall be provided in accordance with the following requirements:

- Designed to comply with Building Code of Australia (BCA) and all relevant Australian Standards.
- Allow storage of all collection bins on site at all times.
- Allow easy access to bins for all waste system users.
- Allow direct and convenient transfer of bins to/from the collection point.
- Appropriately screened to prevent unsightly impacts on amenity.
- Provided with artificial light to enable users to dispose of waste safely and appropriately.
- Sized to accommodate all waste arising on the premises together with any associated waste management equipment
- Concrete (or similar) floor finished to a smooth, even surface, covered at the intersection of walls and plinths.
- Ventilated in accordance with the requirements of the Building Code of Australia and AS1668.2.
- Ventilation openings protected against flies and vermin.
- Provided with tight-fitting doors.
- Provided with adequate bin washing facilities (wall-mounted hot and cold mixing tap with floor graded to wastewater drain with litter trap) in accordance with the relevant authority requirements.

6.2. Bin Colour and Signage Requirements

The collection bins shall be provided in the following colours:

- General waste: dark green or black body with red lid.
- Organics: dark green or black body with light green lid.
- Recycling: dark green or black body with yellow lid.
- Glass: dark green or black body with purple lid.
- Paper & cardboard: dark green or black body with light blue lid.

Bins / bin rooms shall be provided with Sustainability Victoria or equivalent signage (visit: <https://www.sustainability.vic.gov.au/recycling-and-reducing-waste/waste-systems-in-residential-commercial-and-industrial-buildings/waste-signage>).

6.3. Internal Waste Receptacle Requirements

Internal residential waste receptacles shall meet the following requirements:

- General waste: large enough to hold at least 2 days' worth of waste, but no larger than 25 litres.
- Recycling: large enough to hold at least 2 days' worth of recycling, but no larger than 25 litres.
- Glass: large enough to hold at least 2 days' worth of glass (~10 litres).
- Organics: large enough to hold at least 2 days' worth of organics (~10 litres).

Internal commercial waste receptacles shall meet the following requirements:


- All waste streams: no larger than 60 litres to ensure ease of manual handling. Note: if receptacles are larger than 60 litres, a bin lifter may be required within the F&B bin room.

Appendix A : Plans Assessed

GENERAL NOTES

SURVEY:
EXISTING SITE INFORMATION IS TAKEN FROM VERIS SURVEY NUMBER 303981-BG DATED 06/07/2023 AND IS PROVIDED HERE FOR ILLUSTRATIVE PURPOSES ONLY. FOR FULL SURVEY DETAILS REFER TO SURVEY DOCUMENTS PROVIDED WITHIN APPENDICES.

LANDSCAPE DESIGN:
LANDSCAPE DESIGN IS SHOWN INDICATIVELY. FOR FULL LANDSCAPE DETAILS REFER TO LANDSCAPE ARCHITECT'S DOCUMENTATION.



EXISTING TREE WITHIN PROJECT BOUNDARY TO BE RETAINED.
TREE NUMBER, TPZ AND CANOPY AS PER ARBORIST REPORT

ABBREVIATIONS

- AC AIR CONDITIONING CONDENSER UNIT
- COM COMMON RISER
- CL CLOTHES LINE
- ELEC ELECTRICAL RISER
- FEF FIRE EXTINGUISHER
- FFL FINISHED FLOOR LEVEL
- FHR FIRE HOSE REEL
- FHY FIRE HYDRANT
- FIP FIRE INDICATOR PANEL
- HP HOT WATER PUMP
- HYDR HYDRAULIC RISER
- HW HOT WATER UNIT
- NGL NATURAL GROUND LEVEL
- REF REFRIGERANT RISER
- RL RELATIVE LEVEL
- OW OPERABLE WINDOW
- PV PV PANEL
- RFL ROOF LIGHT

MATERIALS


- BRK1 BRICK WORK
- BRK2 HIT & MISS BRICK WORK
- BRK3 GLAZED BRICK
- COM1 CONCRETE PLANTER
- FCS1 PAINTED FIBRE CEMENT SHEET
- T41 EXTERNAL TILE
- SC1 SUN SHADESCREEN
- GL1 DOUBLE GLAZING - CLEAR
- GL2 REEDED GLAZING
- MS1 TENSILE WIRE CABLES
- MS2 MESH FENCING
- MT1 ALUMINIUM (POWDERCOATED DULL BRONZE)
- MT2 ALUMINIUM CANOPY (POWDERCOATED GREEN)
- MT3 PERFORATED ALUMINIUM CLADDING (POWDERCOATED DULL BRONZE)
- SR1 SAFETY GUARD RAIL
- SC1 SUNSHADE SCREEN (GREEN)
- ACP1 ACOUSTIC WALL PANEL
- TM1 PAINTED TIMBER SCREEN
- T11 TILE (GREEN)

- ESD:
1. THE PROJECT ACHIEVES A TOTAL BESS SCORE OF 72% WITH NO MANDATORY CATEGORY (EG. ENERGY, WATER, STORMWATER) BELOW 50%.
 2. 100% OF OUT OF 47 OF THE DEVELOPMENT'S APARTMENTS AND 100% OF OUT OF 20 OF THE DEVELOPMENT'S COMMON AREAS ARE NATURALLY CROSS VENTILATED.
 3. DAYLIGHT MODELLING HAS BEEN CONDUCTED FOR A REPRESENTATIVE SAMPLE OF APARTMENTS. THE SUMMARY RESULTS ARE AS FOLLOWS:
 - *8% OF LIVING FLOOR AREA ACHIEVES >80% ABOVE DF
 - *8% OF BEDROOM FLOOR AREA ACHIEVES >80% ABOVE DF
 - *4% OF NON-RESIDENTIAL AREAS ARE TARGETING A 2% DF TO 40% OF THE NOMINATED AREA.
 4. 38% OF OUT OF 47 OF APARTMENTS ACHIEVE AT LEAST 3 HOURS OF SUNLIGHT.
 5. THE DEVELOPMENT IS PROVIDED WITH A COMPREHENSIVE SHADING STRATEGY.
 6. THE DEVELOPMENT IS TO ACHIEVE A 4 STAR AVERAGE WATERS ENERGY RATING RESULT FOR THE APARTMENTS AND A 7 STAR AVERAGE WATERS ENERGY RATING RESULT FOR THE COMMON AREAS.
 7. THE NON-RESIDENTIAL AREAS AIM TO REDUCE HEATING AND COOLING ENERGY CONSUMPTION BELOW THE REFERENCE CASE (SECTION 2.0.16).
 8. THE DEVELOPMENT IS TO UTILISE ELECTRIC HEAT PUMP HOT WATER SYSTEM.
 9. A BIPHASE SOLAR PV SYSTEM IS TO BE PROVIDED ON THE ROOF OF THE APARTMENT BUILDING.
 10. INDIVIDUAL COLD WATER AND ELECTRICITY METERS WILL BE PROVIDED TO THE APARTMENTS, COMMON AREAS AND COMMUNAL AREAS.
 11. WATER EFFICIENT FITTINGS AND FIXTURES ARE APPLIED THROUGHOUT.
 12. A 32,000 LITRE RAINWATER TANK AND A 30 LITRE RAINWATER TANK WILL HARVEST RAINWATER FROM THE APARTMENT ROOF AND TOWNHOUSE ROOFS RESPECTIVELY. THESE TANKS WILL BE CONNECTED TO ALL TOILETS.
 13. A 4 MEGALITRE RAINWATER TANK ONLY IS PROVIDED.
 14. ALL LANDSCAPING IS TO BE NATIVE SPECIES OR LANDSCAPING IRRIGATION IS TO BE CONNECTED TO THE RAINWATER TANK ONLY.
 15. A MINIMUM OF 67 BICYCLE SPACES ARE TO BE PROVIDED FOR RESIDENTS.
 16. IN TOTAL 2 BICYCLE SPACES ARE TO BE PROVIDED FOR STAFF.
 17. IN TOTAL 14 BICYCLE SPACES ARE TO BE PROVIDED FOR RESIDENTIAL VISITORS AND 7 BICYCLE SPACES ARE TO BE PROVIDED FOR NON-RESIDENTIAL VISITORS.
 18. ONE CHARGING POINT FOR ELECTRICAL VEHICLES IS INTEGRATED IN THE PROPOSED DEVELOPMENT.
 19. 100% OF COMMON SPACE (INCLUDING CLOTHES LINE) WILL BE PROVIDED AT THE APARTMENT BUILDING ROOFTOP DECK.
 20. 22.2% OF COMMON SPACE PRODUCTIVITY AREA WILL BE PROVIDED.
- REFER TO ESD CONSULTANTS DOCUMENTATION FOR FULL DETAILS.

No.	Date	Description
4	03.07.2024	Amended TP Submission for VCAT

TOWN PLANNING

NOT FOR CONSTRUCTION



KTA


Kerstin Thompson Architects Pty Ltd
Wurundjeri Wai Wurrung Country
6 Lothian St, North Melbourne VIC 3051
T +61 3 8662 8800
kta@kerstinthompson.com
www.kerstinthompson.com

DRAWING TITLE
GA PLAN - LEVEL BASEMENT B1

PROJECT
97 Aims Road
AT St Kilda East
FOR Neometro

DATE	DRAWN BY	DRAWING NO.	REV.
03.07.2024	KTA		
SCALE	PROJECT		
As indicated(A1)	2202	TP1B1	4

Copyright 2024






GENERAL NOTES

SURVEY:
EXISTING SITE INFORMATION IS TAKEN FROM VERIS SURVEY NUMBER 303981-BG DATED 06/07/2023 AND IS PROVIDED HERE FOR ILLUSTRATIVE PURPOSES ONLY. FOR FULL SURVEY DETAILS REFER TO SURVEY DOCUMENTS PROVIDED WITHIN APPENDICES.

LANDSCAPE DESIGN:
LANDSCAPE DESIGN IS SHOWN INDICATIVELY. FOR FULL LANDSCAPE DETAILS REFER TO LANDSCAPE ARCHITECT'S DOCUMENTATION.



ABBREVIATIONS

- AC AIR CONDITIONING CONDENSER UNIT
- COM COMMS RISER
- CL CLOTHES LINE
- ELEC ELECTRICAL RISER
- FEX FIRE EXTINGUISHER
- FFL FINISHED FLOOR LEVEL
- FHR FIRE HOSE REEL
- FHY FIRE HYDRANT
- FIP FIRE INDICATOR PANEL
- HP HOT WATER PUMP
- HYDR HYDRAULIC RISER
- HW HOT WATER UNIT
- NGL NATURAL GROUND LEVEL
- REF REFRIGERANT RISER
- RL RELATIVE LEVEL
- OW OPERABLE WINDOW
- PV PV PANEL
- RLF ROOF LIGHT


MATERIALS

- BRK1 BRICK WORK
- BRK2 HIT & MISS BRICK WORK
- BRK3 GLAZED BRICK
- COM1 CONCRETE PLANTER
- FCB1 PAINTED FIBRE CEMENT SHEET
- TL1 EXTERNAL TILE
- SC1 SUN SHADESCREEN
- GL1 DOUBLE GLAZING - CLEAR
- GL2 REEDED GLAZING
- MS1 TENSILE WIRE CABLES
- MS2 MESH FENCING
- MT1 ALUMINIUM POWDERCOATED DULL BRONZE
- MT2 ALUMINIUM CANOPY (POWDERCOATED GREEN)
- MT3 PERFORATED ALUMINIUM CLADDING
- REF REFERENCE COLOURED DULL BRONZE
- SR1 SAFETY GUARD RAIL
- SC1 SUNSHADE SCREEN (GREEN)
- ACPH ACOUSTIC WALL PANEL
- TM1 PAINTED TIMBER SCREEN
- TL1 TILE (GREEN)

- ESD:
1. THE PROJECT ACHIEVES A TOTAL BESS SCORE OF 70% WITH NO MANDATORY CATEGORY (60) ENERGY WATER STORAGE BELOW 50%.
 2. 100% OF OUT OF 47) OF THE DEVELOPMENT'S APARTMENTS AND 100% (20) OUT OF 30) OF THE DEVELOPMENT'S TOWNHOUSES ARE NATURALLY CROSS VENTILATED.
 3. DAYLIGHT MODELLING HAS BEEN CONDUCTED FOR A REPRESENTATIVE SAMPLE OF APARTMENTS. THE SUMMARY RESULTS ARE AS FOLLOWS:
 - 88% OF LIVING FLOOR AREA ACHIEVES >80% ABOVE DF
 - 88% OF BEDROOM FLOOR AREA ACHIEVES >80% ABOVE DF'S
 4. THE NON-RESIDENTIAL AREAS ARE TARGETING A 2% DF TO 40% OF THE HOUSING AREA.
 5. 38% (18) OUT OF 47) OF APARTMENTS ACHIEVE AT LEAST 3 HOURS OF SUNLIGHT.
 6. THE DEVELOPMENT IS PROVIDED WITH A COMPREHENSIVE SHADING STRATEGY.
 7. THE DEVELOPMENT IS TO ACHIEVE A 4 STAR AVERAGE BATTERS ENERGY RATING RESULT FOR THE APARTMENTS AND A 7 STAR AVERAGE BATTERS ENERGY RATING RESULT FOR THE TOWNHOUSES.
 8. THE NON-RESIDENTIAL AREAS AIM TO REDUCE HEATING AND COOLING ENERGY CONSUMPTION BELOW THE REFERENCE CASE (RCA) SECTION 2.0(16).
 9. THE DEVELOPMENT IS TO UTILISE ELECTRIC HEAT PUMP HOT WATER SYSTEM.
 10. A BATH ROOM FLOOR SYSTEM IS TO BE LOCATED ON THE ROOF OF THE APARTMENT BUILDING.
 11. A 300V SOLAR PV SYSTEM IS TO BE PROVIDED FOR EACH TOWNHOUSE.
 12. INDIVIDUAL COLD WATER AND ELECTRICITY METERS WILL BE PROVIDED TO THE APARTMENTS, TOWNHOUSES AND COMMUNAL AREAS.
 13. WATER EFFICIENT FITTINGS AND FIXTURES ARE APPLIED THROUGHOUT.
 14. A 20,000 LITRE RAINWATER TANK AND A 30 LITRE RAINWATER TANK WILL MARKET STANDARD FROM THE APARTMENT ROOF AND TOWNHOUSE ROOFS RESPECTIVELY. THESE TANKS WILL BE CONNECTED TO ALL TOILETS.
 15. A CONNECTED TO THE RAINWATER TANK ONLY.
 16. ALL LANDSCAPING IS TO BE NATIVE SPECIES OR LANDSCAPING IRRIGATION IS TO BE CONNECTED TO THE RAINWATER TANK ONLY.
 17. A MINIMUM OF 67 BICYCLE SPACES ARE TO BE PROVIDED FOR RESIDENTS.
 18. IN TOTAL 2 BICYCLE SPACES ARE TO BE PROVIDED FOR STAFF.
 19. IN TOTAL 14 BICYCLE SPACES ARE TO BE PROVIDED FOR RESIDENTIAL VISITORS AND BICYCLE SPACES ARE TO BE PROVIDED FOR NON-RESIDENTIAL VISITORS.
 20. ONE CHARGING POINT FOR ELECTRICAL VEHICLES IS INTEGRATED IN THE PROPOSED DEVELOPMENT.
 21. 60M² OF COMMUNAL SPACE (INCLUDING CLOTHES LINE) WILL BE PROVIDED AT THE APARTMENT BUILDING ROOFTOP DECK.
 22. 2% OF COMMUNAL FLOOR PRODUCTION AREA WILL BE PROVIDED.
- REFER TO ESD CONSULTANTS DOCUMENTATION FOR FULL DETAILS.

No.	Date	Description
4	03/07/2024	Amended TP Submission for VCAT

TOWN PLANNING
NOT FOR CONSTRUCTION



KTA

Kerstin Thompson Architects Pty Ltd
Wurundjeri Wai Wurung Country
6 Lothian St, North Melbourne VIC 3051
T +61 3 8662 8800
kta@kerstinthompson.com
www.kerstinthompson.com

DRAWING TITLE
GA PLAN - LEVEL GROUND




PROJECT
97 Aims Road
AT
St Kilda East
FOR
Neometro

DATE	DRAWN BY	DRAWING NO.	REV.
03/07/2024	KTA	TP100	4
SCALE	PROJECT		
As indicated(A1)	2202		


GA PLAN - LEVEL GROUND
SCALE 1:200

Appendix B : Waste Collection Vehicle Swept Path Assessment

C:\USERS\JACKSON\HAMILL-BEACH\RATIO CONSULTANTS\19329T - GENERAL\DESIGN SKETCH ADVICE (INCLUDING SWEEP PATHS)\SK10 - [2024.05.22]\19329T-SK10.DWG
 27/05/2024 2:53:19 PM
 Document Set ID: 8249557




RATIO CONSULTANTS PTY LTD
 ABN 005 422 104
 8 GWYNNE STREET
 CREMORNE, VICTORIA 3121
 TELEPHONE (03)9429 3111
 FACSIMILE (03)9429 3011




Proposed Residential Development
 97 Alma Road, St Kilda East
 Swept Path Assessment - Ground Level

NOTE:
 1) Base Plan Supplied by Kerstin Thompson Architects Pty Ltd, dated 20 May 2024
 2) Maximum Design Speed 5km/h

RATIO REFERENCE 19329T-SK10/JHB	SHEET No. 03 of 07	SCALE 1:200@A3	DATE 27/05/2024
------------------------------------	-----------------------	-------------------	--------------------



G:\USERS\JACKSON\HAMIL-BEACH\RATIO CONSULTANTS\19329T-SK10 - [2024.05.22]\19329T-SK10.DWG
 27/05/2024 2:53:21 PM
 RATIO CONSULTANTS PTY LTD
 ABN 005 422 104
 8 GWYNNE STREET
 CREMORNE, VICTORIA 3121
 TELEPHONE (03)9429 3111
 FACSIMILE (03)9429 3011
 Document Set ID: 8249557
 Version: 1, Version Date: 14/08/2024



RATIO CONSULTANTS PTY LTD
 ABN 005 422 104
 8 GWYNNE STREET
 CREMORNE, VICTORIA 3121
 TELEPHONE (03)9429 3111
 FACSIMILE (03)9429 3011
 Document Set ID: 8249557

Mini-Rear Loader Waste Collection Vehicle


VEHICLE ENVELOPE (FORWARD)
 300mm CLEARANCE (FORWARD)
VEHICLE ENVELOPE (REVERSE)
 300mm CLEARANCE (REVERSE)

Overall Length 6.345m
 Body Width 1.700m
 Overall Body Height 2.080m
 Min Body Ground Clearance 0.205m
 Track Width 1.670m
 Lock to Lock Time 4.00 sec
 Curb to Curb Turning Radius 6.450m


Proposed Residential Development
 97 Alma Road, St Kilda East
 Swept Path Assessment - Basement Level

NOTE:
 1) Base Plan Supplied by Kerstin Thompson Architects Pty Ltd, dated 20 May 2024
 2) Maximum Design Speed 5km/h


RATIO REFERENCE 19329T-SK10/JHB	SHEET No. 04 of 07	SCALE 1:200@A3	DATE 27/05/2024
------------------------------------	-----------------------	-------------------	--------------------



G:\USERS\JACKSON.HAMILL\BEACH.RATIO CONSULTANTS\19329T - GENERAL DESIGN SKETCH ADVICE (INCLUDING SWEEP PATHS)\SK10 - [2024.05.22]\19329T-SK10.DWG
 27/05/2024 2:53:26 PM
 FACSIMILE 039429 3111
 Document Set ID: 8249557



RATIO CONSULTANTS PTY LTD
 ABN 005 422 104
 8 GWYNNE STREET
 CREMORNE, VICTORIA 3121
 TELEPHONE (03)9429 3111
 FACSIMILE 039429 3111



Proposed Residential Development
 97 Alma Road, St Kilda East
 Swept Path Assessment - Basement Level

NOTE:
 1) Base Plan Supplied by Kerstin Thompson Architects Pty Ltd, dated 20 May 2024
 2) Maximum Design Speed 5km/h

RATIO REFERENCE 19329T-SK10/JHB	SHEET No. 05 of 07	SCALE 1:200@A3	DATE 27/05/2024
------------------------------------	-----------------------	-------------------	--------------------

